

Bill Of Quantity
PEKERJAAN JARINGAN FIBER OPTIC
RSUD K.R.M.T. WONGSONEGORO SEMARANG

No	Nama Barang	Qty	Sat	Satuan Harga (Rupiah)	Total Harga (Rupiah)
A Pekerjaan Persiapan					
1	Pekerjaan papan nama dan K3 dan perapian	1	Ls	-	-
2	Perapian kembali ex, bongkaran	1	Ls	-	-
3	Administrasi dan dokumentasi (laporan, Training, asbuilt drawing , shop drawing, dokumentasi	1	Ls	-	-
				Sub Total A	-
B Perangkat Aktif					
1	Core Switch	1	unit	-	-
2	Distribution Switch 12 SFP+	1	unit	-	-
3	Distribution Switch 8 SFP+	1	unit	-	-
4	Access Switch 24 ports	8	unit	-	-
5	Access Switch 48 ports	7	unit	-	-
6	Access Point	22	unit	-	-
7	Access Point high density	4	unit	-	-
8	Stack Cable Access Switch	2	pcs	-	-
9	Module 10G SM	30	pcs	-	-
				Sub Total B	-
C Fiber Optik & Aksesoris					
1	Kabel Fiber Optik SM 12 Core Armored	4000	mtr	-	-
2	OTB Rackmount 144F (Lengkap Pigtail & Adapter)	2	unit	-	-
3	OTB Rackmount 48F (Lengkap Pigtail & Adapter)	5	unit	-	-
4	OTB Rackmount 24F (Lengkap Pigtail & Adapter)	4	unit	-	-
5	OTB Rackmount 12F (Lengkap Pigtail & Adapter)	12	unit	-	-
6	Patch Cord SM	44	pcs	-	-
7	Wallmount Rack 12U	21	unit	-	-
8	Standing Rack	1	unit	-	-
9	UTP Cable Cat 6	6	box	-	-
10	Kabel Tray	50	btg	-	-
				Sub Total C	-
D Instalasi					
1	Instalasi kabel FO lewat Tray/Conduit	4000	mtr	-	-
2	Jointing Fiber Optik	258	core	-	-
3	Instalasi rack system	22	Ttk	-	-
4	Instalasi electrical	21	ttk	-	-
5	Instalasi UTP & AP	26	ttk	-	-
				Sub Total D	-
				Total termasuk pajak	-

Terbilang :

CV/PT.

.....